



TENDER NOTICE

The BEDC Electricity PLC intends to undertake the following projects:

- Lot 1: Rehabilitation of Refinery 2 33kV Feeder in Warri Region;
- Lot 2: Rehabilitation of Osubi 33kV Feeder in Warri; and
- Lot 3: Rehabilitation of 1.75Km Guinness 33kV Feeder.

Interested and reputable vendors are invited to submit their quotations for any **one** of Lots 1-3 in writing, with all costs clearly stated in Naira.

Vendors are advised to liaise with the Technical Services Department to conduct a site visit prior to the submission of quotations and to visit the Procurement Unit, Room A12, to obtain the Bill of Materials in Excel format.

Any contractor who fails to physically visit the site will be disqualified. All materials required for the job shall be provided by the vendor.

The Commercial Bid, including a covering letter and the Bill of Quantities, must be clearly typed and duly signed. Failure to comply with these instructions will result in automatic disqualification.

Your submission should be addressed to:

**The Managing Director,
BEDC Electricity PLC,
5 Akpakpava Road,
Benin City.**

Attention: Head, Services.

Bids should be submitted **electronically** via the e-mail address **mtc@beninelectric.com** not later than **6:00 pm on Friday, February 6, 2026**.

Kindly note that copying any staff e-mail address is strictly prohibited and will result in automatic disqualification.

For enquiries, kindly contact:

 **bidders@beninelectric.com**

MANAGEMENT

29/01/2026

BILL OF QUANTITIES FOR REHABILITATION OF REFINERY 2 33KV FEEDER - LOT 1

VENDOR NAME:

MATERIAL REQUIREMENTS									
S/N	MATERIALS	UNIT	QTY	RATE	TOTAL	ERECTION	TRANSPORTATION	AMOUNT	REMARK
1	33kV Gang Isolator	No	1		0.00			0.00	
2	33kV Pot Insulator	No	35		0.00			0.00	
3	Copper Wire 70mm2	Mtrs	20		0.00			0.00	
4	9ft Fibre Cross Arm	No	30		0.00			0.00	
5	Cable Lugs 70mm2	No	15		0.00			0.00	
6	150mm2 All Aluminum Conduc	Mtrs	3000		0.00			0.00	
7	Trace Clearing	Km	5		Nil	0.00	Nil	0.00	
TOTAL					0.00	0.00	0.00	0.00	
Contingency (5%)								0.00	
Total + Contingency								0.00	
Add VAT 7.5%								0.00	
Bid Price								0.00	

CONTACT NAME:.....

SIGNATURE:.....

DATE:.....



BEDC ELECTRICITY PLC

BILL OF QUANTITIES FOR THE REHABILITATION OF OSUBI 33KV FEEDER - LOT 2

VENDOR NAME:

MATERIAL REQUIREMENTS									
S/N	MATERIALS	UNIT	QTY	RATE	TOTAL	ERECTION	TRANSPORTATION	AMOUNT	REMARK
1	150mm2 Aluminum Conductor.	Mtr	3800	BEDC	BEDC			0.00	To be provided by BEDC
2	95mm2 Recline Wire	Mtr	3000	BEDC	BEDC			0.00	To be provided by BEDC
3	33kV Silicon Disc Insulator	No	124		0.00			0.00	
4	33kV Silicon Pot insulator	No	124		0.00			0.00	
5	33KV Gang Isolator.	No	4		0.00			0.00	
6	HT Concrete Poles 40ft.	No	10		0.00			0.00	
7	HT Concrete Poles 34ft.	No	15		0.00			0.00	
8	Channel Iron 9ft.	No	100		0.00			0.00	
9	33kV Tie- Strap	No	85		0.00			0.00	
10	Complete Stay set	No	20		0.00			0.00	
11	5/8X 6" Bolts & Nuts.	No	30		0.00			0.00	
12	5/8X 9" Bolts & Nuts.	No	30		0.00			0.00	
13	5/8X 10" Bolts & Nuts.	No	30		0.00			0.00	
14	5/8X 12" Bolts & Nuts.	No	30		0.00			0.00	
15	Commissioning	No	30		Nil	0.00	Nil	0.00	
TOTAL					0.00	0.00	0.00	0.00	
Contingency (5%)								0.00	
Total + Contingency								0.00	
Add VAT 7.5%								0.00	
Bid Price								0.00	

CONTACT NAME:.....

SIGNATURE:.....

DATE:.....



BEDC ELECTRICITY PLC

BILL OF QUANTITIES FOR THE REHABILITATION OF 1.75KM GUINNESS 33KV FEEDER - LOT 3

VENDOR NAME:

MATERIAL REQUIREMENTS									
S/N	MATERIALS	UNIT	QTY	RATE	TOTAL	ERECTION	TRANSPORTATION	AMOUNT	REMARK
1	150sq.mm ACSR Conductor	Mtrs	5600		0.00			0.00	To be provided by BEDC
2	10.36m RCC Pole(34ft)	No	42		0.00			0.00	To be provided by BEDC
3	20Ft. Galvanised Pipe	Length	1		0.00			0.00	
4	33KV Composite Silicon Insulators	No	95		0.00			0.00	
5	33KV Silicon Tension Insulator	No	24		0.00			0.00	
6	33KV Silicon Tension Set	No	24		0.00			0.00	
7	33KV Channel Iron	No	18		0.00			0.00	
8	Line Taps	No	42		0.00			0.00	
9	Bolt & Nut 5/8x11	No	153		0.00			0.00	
10	Washers	No	210		0.00			0.00	
11	Earth Rods	No	6		0.00			0.00	
12	Sky Wire(Earthing)	Mtrs	27		0.00			0.00	
13	33kv Stay Set Complete	No	14		0.00			0.00	
14	Stay Wire	Mtrs	210		0.00			0.00	
15	Danger Plate	No	42		0.00			0.00	
16	Anti-climbing device	No	42		0.00			0.00	
17	33KV Gang Isolator	No	1		0.00			0.00	
				TOTAL	0.00	0.00	0.00	0.00	
								Contingency (5%)	0.00
								Total + Contingency	0.00
								Add VAT 7.5%	0.00
								Bid Price	0.00

CONTACT NAME:.....

SIGNATURE:.....

DATE:.....